



TRUNKING AND TRAY DETAIL



NOTE: THE ELECTRICAL INSTALLATION IN THIS BUILDING MUST COMPLY WITH THE 4TH EDITION OF THE ETCI WIRING REGULATIONS.

PLEASE ENSURE THAT ADEQUATE ALLOWANCE HAS BEEN MADE FOR PROVISION OF RCDs, RCBOs, GALVANISED CONDUIT DROPS ETC.



NOTES

1. NOTES ON ALL DRAWINGS APPLY WHERE APPROPRIATE.

DISTRIBUTION BOARDS TO SERVICE THE FOLLOWING:

- 'C' - FRONT OF HOUSE LIGHTING BASEMENT & G.F.
- 'D' - FRONT OF HOUSE POWER BASEMENT & G.F.

WASTE WATER PUMP SUPPLIED AND INSTALLED IN BASE OF FIRE FIGHTING LIFT PIT UNDER THIS CONTRACT INCLUDING PIPE WORK AND CONNECTION TO THE MAIN WASTE SYSTEM IN THE BASEMENT CEILING VOID PUMP AS ABB MF 324WMS

PHONE OUTLET FOR
FIRE ALARM PANEL.

DOUBLE SOCKET OUTLETS
STARCORE TO BE SPLIT IN
TWO RING CIRCUITS
LVLS B'MENT-3RD D/3/L1
LVLS 4TH-ROOF D/4/L3

B-11-L123
① 16A SUPPLY FOR HOIST
TPN


SUPPLIES TO AUTOMATIC DOORS IN
CELLING VOID WITH ASSOCIATED FIRE
ALARM INTERFACES, 2NO. 8 CORE
CONTROL CABLING FROM EACH
DOOR TO BEHIND RECEPTION UNDER
THIS CONTRACT, CONTROLLER BY
OTHERS.

12AW ELECTRIC AIR CURTAIN
UNDER THIS CONTRACT AS
TEKADOOR ZEPHYR EC S
COMPLETE WITH CEILING
RECESSING KIT, 5 STEP TRONIC
EC CONTROLLER AND ROOM
THERMOSTAT. MAIN CONTROLLER
TO BE INSTALLED IN RECEPTION.
TO BE SUPPLIED WITH FIRE
ALARM INTERFACE TO ISOLATE
SUPPLY DURING FIRE ALARM.

UNDERSIDE OF TABLE FOR
FIXED TABLET.

HANGING SCREEN SERVICES TO BE CONCEALED IN THE CEILING VOID.

REFER TO DRAWING 3682-E502
FOR BAR & RECEPTION LAYOUTS



INCLUDE ALL NECESSARY OFFSETS OF SERVICES IN CEILING VOIDS, SERVICE DUCTS AND ALL OTHER AREAS TO ACHIEVE CROSSOVERS AND CO-ORDINATION OF MECHANICAL AND ELECTRICAL SERVICES.

Caldwell

ARCHITECT
ICA ARCHITECTS

**JOB
FINDLATER HOUSE DUBLIN
HOLIDAY INN EXPRESS**

DRAWING ELECTRICAL SERVICES INSTALLATION

**GENERAL PURPOSE SOCKET OUTLETS,
SMALL POWER AND SPECIALIST SYSTEMS
GROUND FLOOR**

DRAINING NO./VERSION
3682/E202
C5

REQ. DATE	DESCRIPTION	DR	CK
C5 06.06.16	ARCH LAYOUT REVISED	MQ	MB
C4 26.04.16	GENERAL POWER REVISED	MQ	MB
C3 30.03.16	ARCH LAYOUT REVISED	DW	MB
C2 16.10.15	ARCH LAYOUT REVISED	DW	MB
C1 12.05.15	G4 CONSTRUCTION ISSUE	DW	MB
T1 15.01.15	TENDER ISSUE	DW	MB

UNIT 6 FORESGROVE BUSINESS PARK TEL (028)90699720 FAX (028)9064162
 NEWTOWNBREDA BT8 6AW EMAIL: admin@caldwellconsulting.net